



06/25/2021

Mr. Keith R. Allison

Environmental Inspector
WV Department of Environmental Protection
Division of Water and Waste Management
22288 Northwestern Pk
Romney, WV 26757.

Dear **Mr. Allison**,

The ROCKWOOL, Ranson facility would like to inform you of two projects that are being completed onsite. As part of our routine preventative maintenance and facility inspection activities we have identified two areas that will require the facility to preform the work outlined below:

PM 1-We have tasked a local contractor to scope our stormwater pipes with the use of cameras to verify proper installation and integrity during precipitation events.

PM 2-We have identified an area on the bank of our reuse pond that will require modifications to ensure we are not allowing water to form under the liner. The actions below will be complete.

- Repair (1) 8" x 6" section in the HDPE liner of Reuse Pond up above the anchor trench berm near the pump pad
- Dig a 10'x15' footprint on both the south and north side of the settling basin/weir of the reuse pond in preparation of extending the batten bar/HDPE liner further into the anchor trench to mitigate any future risk of water getting under the liner.
- Repair (1) 6" x 6" section in the HDPE liner of Stormwater Detention pond near the anchor trench berm above any water elevations

Please do not hesitate to contact me directly should you have any questions.

Sincerely,

Ryan Durrill
SHEQ Manager